



# Ector County Health Department

221 N. Texas  
Odessa, TX 79761  
(432) 498-4141

## Notice of Approval & Permission to Backfill an On-Site Sewage Facility PERMIT #: 11842

Location: 16690 Basin W. #2, Odessa, TX 79763-  
Lot 3 Block 1 Basin Industrial Addition  
Owner: John Loepky  
Mailing address: 430 US Hwy 180 W, Seminole TX, 79360-

Type of OSSF: Treatment Type: Septic  
Disposal Type: Soil Sub & LC Panels  
Maximum Flow: 200 Gallons per Day  
Tank Size: 1200 Gallon Tank(s)  
Drainfield: 24 - Feet of Panels

This serves to notify all persons that the on-site sewage facility owned by the above has been approved, satisfying design, construction, and installation requirements of the Texas Commission on Environmental Quality (TCEQ) to the point that it may be backfilled in order to fulfill further installation requirements.

This On-Site Sewage Facility Permit and Permission to Backfill is issued for the installer to backfill the above-identified on-site sewage facility. **Further requirements indicated below must be completed and observed in a final inspection before a License to Operate may be issued.**

The issuance of this Permission to Backfill an on-site sewage facility shall only indicate that the facility meets the minimum requirements for issuance of this permission.

State standards do not guarantee that an on-site sewage facility will perform satisfactorily under all conditions. It is the responsibility of the owner to maintain and operate the facility in a satisfactory manner.

Any modifications to the size of the business or alteration of the septic system requires a new permit. The sewer lines are required to be protected from crushing by vehicular drive-over, using either Schedule 80 PVC or sleeved in Schedule 40 PVC. The tank(s) and drainfield shall have metal posts or other permanent diversionary devices installed around their exposed perimeter as vehicular drive-over protection. The installer or owner is required to provide ECHD with 2 photographs during the backfilling process at approximately the 1/3 and 2/3 completion points to confirm suitable soil is being used. Water supply lines are required to be placed at least 10 feet from sewer lines and any part of the OSSF. Water lines shall not cross sewer lines unless they have been engineered to meet TAC Chapter 290.

**Additional Requirements:** Please contact your inspector for a final inspection when you have constructed the drive-over protection or alternatively, e-mail us photos of the drive-over protection. Your inspector would have either been Gregg at 617-8405, gregg.olberts@ectorcountytexas.gov; Divina at 617-8406, divina.bongo@ectorcountytexas.gov, Brandy at 617-8407, brandy.garcia@ectorcountytexas.gov, Rashmi at 617-8409, rashmi.deshmukh@ectorcountytexas.gov or Nessa at 617-8408, lutfor.nessa@ectorcountytexas.gov

*Kelby Upchurch D.R. OS0035616*  
Agency

7-26-2022  
Date